

**BID IDENTIFICATION NO: BP -I/14/2019-20 dt.30.10.2019.**



ODISHA TOURISM DEVELOPMENT CORPORATION LIMITED  
(A Govt. of Odisha Undertaking)

Panthanivas (Old Block): Lewis Road: Bhubaneswar-14

**DETAILED TENDER CALL NOTICE FOR THE WORK:-**

**“ ORGANIZATION OF KONARK FESTIVAL AT  
KONARK 2019”**

**ODISHA TOURISM DEVELOPMENT CORPORATION LIMITED**  
**(A Government of Odisha Undertaking)**  
**Panthanivas [Old Block], Lewis Road, Bhubaneswar-751014**  
**TENDER CALL FOR ORGANIZATION OF KONARK FESTIVAL- 2019**

On behalf of Department of Tourism, Govt. of Odisha, Odisha Tourism Development Corporation is going to organize Konark Festival (A festival of classical dances of India) in the Open Air Auditorium at Konark from 1<sup>st</sup> to 5<sup>th</sup> December 2019 . Offers are invited from reputed firms/ agencies having experience and expertise in making Light, sound and other ancillary arrangements in classical Dance festival. Offers should be submitted in two bids-“**Technical Bid**” with required documents and “**Financial Bid** ” in the prescribed format. The tender paper will be received up to 11.00 AM of 11.11.2019 at OTDC Head office by Speed Post/ Registered Post/ in Tender Box in office only. OTDC will not be held responsible for any postal delay. Technical bids will be opened first on the same day at 12.00 Noon followed by opening of Financial Bids of those who will fulfill the eligibility criteria of Technical Bid. The tenderers or their authorized representatives may remain present during the opening of bids. The covers should be sealed and super-scribed in bold letters “**Technical Bid**” / “**Financial Bid**” of Organization of Konark Festival, 2019. Any Addendum / Corrigendum / Cancellation can be seen in the website.

The Authority reserves the right to reject any or all offers without assigning any reason thereof & is not under any obligation to accept the lowest offer.

<b>Eligibility Criteria</b>	<b>Documents required for Pre-qualification</b>
1. Experience in making Stage Light, sound and other ancillary arrangement for <b>Similar Classical programme</b> for any Govt./ Semi Govt./ Corporate Office/ Any other reputed organization. [(individual work order should be not less than Rs.20.00 lakhs at least (One) 1 in last 3 years) 2. Minimum average annual Turnover for similar work not less than Rs.30.00 lakhs during last 3years.	1. EMD of Rs.1,00,000/-in shape of D.D. drawn on any nationalized Bank in favour of Managing Director, OTDC Ltd. 2. Copy of valid GST Registration Certificate. 3. Participation fee (non-refundable) of Rs.5000/-in shape of DD drawn in favour of M.D. OTDC. 4. Copy of the profit & Loss A/C certificate by the chartered Accountant confirming the annual turnover of last 3 years ending on 31.3.2019. 5. Copy of the work order confirming execution of similar work not less than Rs.20.00 lakh. 6. Copy of the PAN.

**Superintending Engineer**  
**OTDC Ltd.**

## A. STAGE LIGHT

SL.No	ITEM	Quantity	Unit	Amount (in Rs.)
1.	PAR 64 –1 kw [Osram,Sylvania or GE Bulb only], [Bulb—CP 60, 61&62]	150	Nos.	
2	Multy 20 with barn doors	8	Nos.	
3	2kw Solar (Canara Brand)	4	Nos.	
4	SGM Follow Spot	2	Nos.	
5	Pointy Light	8	Nos.	
6	Citi Colour	6	Nos.	
7	Sharpy	7	Nos.	
8	4.00KW HMI PAR for Temple	4	Nos.	
9	4.00KW HMI Fresnel for Temple (CANARA BRAND)	2	Nos.	
10	Smoke machine	4	Nos.	
11	Haze Machine with fan	4	Nos.	
12	Jumbo Strobe Light	4	Nos.	
13	LED Par 3W	40	Nos.	
14	Halogen Light 1 KW for Auditorium & others	15	Nos.	
15	Table lamp for musicians with CFL Bulb	12	Nos.	
16	Operating Console for par and other lights[Avolite pearl 2010] with programmer	2	Nos..	
17	Appropriate DMX operating console for Sharpy & Moving Head	1	Nos.	
18	Appropriate DMX operating console for LED par	1	Nos.	
19	Sound less Generator 125 KVA including fuel [only for stage lighting]. The Generator will operate from 4.00 P.M. for 08hrs.	2	Nos.	
20	III phase changeover	2	Nos.	

21	Profile Light with Irish Control & Gobo Holder	10	Nos.	
22	1 KW Baby Fresnel with Buander (CANARA BRAND)	4	Nos.	
23	Sky Taker 2500 W	1	Nos.	
24	Generator [10 KVA] & required cabling for Sky Taker including fuel. THE Generator will operate from 04.00 for 06hrs.	1	Nos.	
25	Platform with ladder for urgent repair/ replacement	1	LS	
26	Led Profile Spot	4	Nos.	
27	Colour Blinder light	8	Nos.	
28	Blinder Light	4	Nos.	
			<b>TOTAL - A</b>	

## B. STAGE SOUND

Sl. No	ITEM	Quantity	Unit	Amount (in Rs.)
1	Line Array 4000W/5000W including all equipments for the system for both side of Stage.	1	Set	
2	JBL 712 Monitor with matching amplifier (Philips/Sunodyne) 500 watt RMS.	12	Nos.	
3	Microphones (Shure/ AKG/ Senheiser)	25	Nos.	
4	Cordless Microphones ( Shure/ Sony/ Senheiser)	4	Nos.	
5	Effect Processor Yamaha SPX 2000	1	Nos.	
6	Equalizer BSS Opal Model/ DBX 231	2	Nos.	
7	JBL Cross Over	1	Nos.	
8	Digital / Analogue Mixer ( Yamaha / Mackie / Sound craft ) of adequate capacity to meet the requirement of stage sound. (32 Channels)	1	Set	
9	Microphone Stands	20	Nos..	

10	Snake Cable as per requirement	1	Set	
11	CD/DVD Player (Sony/Philips.)	2	Nos.	
12	125KVA Generator (Soundless) for sound for cultural programme with fuel. The generator will operate from 04.00 PM for 08hrs.	1	No.	
13	Inear Earphone with Amplifier	25	Nos.	
14	Audio and video recording of each day programme, in CD format.	5	Days	
			<b>TOTAL - B</b>	

### C. ILLUMINATION

Sl. No	ITEM	Quantity	Unit	Amount (in Rs.)
1	Halogen Light ( 1KW )	20	Nos.	
2	Metal Halide (400 W)	60	Nos.	
3	Metal Halide Light ( color)( 400W)	150	Nos.	
4	Colour Bulb (each chain should be 50Nos. bulb)	100	Chains	
5	Tuni Light (each chain should be 100Nos. bulb)	200	Nos.	
6	LED display Panel of size 12' X 8' with cabling including all arrangements and watch & ward	4	Nos.	
7	LED Pipe Light ( in different colors)	600	Rmt.	
8	Long Lamp shed of Applique works	50	Nos.	
9	Small Lamp shed of Applique work.	1200	Nos.	
10	Medium size Umbrella of Applique works	200	Nos.	
11	Medium size lamp shed with Applique works	300	Nos.	
12	LED Lichu chain ( blue, white, pink, red and green.)	1500	Chains	
13	LED City Colour	10	Nos.	
14	62.5/63KVA Generator with fuel and cabling for illumination of temple from 04.00PM to 11.00PM.	1	Nos.	
15	250KVA Generator with fuel and cabling for Ambience from 04.00PM for 08hrs.	1	Nos.	

16	PAR Light for pathway	50	Nos.	
17	Light tower for parking 5' X 5' X 15' with 10Nos.. of Metal halide of 400W each.	1	Nos.	
20	Ethnic Light Post	80	Nos.	
21	Illumination of Yatrinivas Building, Gitanjali Restaurant and wooden Restaurant, Chandrabhaga with 02 matching colour LED Litchu	3000	Chains	
			<b>TOTAL - C</b>	

## D. GENERAL AMBIENCE CREATION AND OTHER ARRANGEMENTS

Sl. No	ITEM	Quantity	Unit	Amount (in Rs.)
1	Signage 6'X 3'to be displayed at Konark made of flex with wooden frame	18	Nos..	
2	Sitting Arrangements for Distinguished Visitors and Tourists for 7days.			
a.	Cotton Gaddi (width-1'6' )	350	Nos..	
b.	Round pillow	100	Nos..	
c.	Pillow Cover (New to be changed daily.)	100	Nos..	
d.	White Bed sheet ( New to be changed daily)	350	Nos..	
e.	Durry	16	Nos..	
f.	Cloth Mat	5500	Rft.	
g.	Blow plastic Chair	800	Nos..	
h.	Banquet Chair/ Steel Cushion Chair with white Cover	600	Nos.	
i.	Steel Sofa (3 Seater)	30	Nos.	
j.	Steel Sofa (1 Seater)	20	Nos.	
k.	New White Towel for Sofa	120	Nos.	
3	Platform for Musicians (16' -0''X 4'-0''X 0'-6'') made of 19mm ply and carpeting	1	No.	
4	Platform for Lord Jagannath ( 10'-0''X4'-0''X1'-0'') made of 19mm ply & carpeting.	1	No.	
5	Sun Board signage (3'-0X2'0'')	16	No.	
6	Standies of iron frame with both side flex (4'-0''X4'-0''X4'-0'')	4	Nos..	

7	Watch & Ward for Auditorium area and Entry gate for 6days			
	"A" Shift	6	Nos..	
	"B" Shift (4Nos..lady Security)	35	Nos..	
	"C" Shift	8	Nos..	
8	Sweepers:			
	"A" Shift	8	Nos..	
	"B" Shift	8	Nos..	
9	Big Dustbins	15	Nos..	
10	Erection of Service Stall of Size 10'X10' (Ethnic design) - close to Auditorium: Platform on strong wooden base of 6" height & 3 side wall with 4mm. thick ply with wooden frame of 8' height painted & covered with matching carpet on floor, 4Nos.. of tube light & 1 No. 15Amp. Plug point with all fittings and wiring etc. 1No. Smooth Wooden counter with white cloth cover. Size-8'X2'x3' and shelves at the back. Roofing: Tarpaulin roofing with Cotton cloth interior ceiling.	5	Nos..	
11	Erection of food Stall of Size 15'X15' (Ethnic design) close to Auditorium: Platform on strong wooden base of 6" height & 3 side wall with 4mm. thick ply with wooden frame of 8' height painted & covered with matching carpet on floor, 4Nos.. of tube light & 1 No. 15Amp. Plug point with all fittings and wiring etc. 1No. Smooth Wooden counter with white cloth cover. Size- 8'X2'x3' and shelves at the back. Roofing: Tarpaulin roofing with Cotton cloth interior ceiling.	1	No.	
12	Arrangements for Light & sound operators, Doordarshan staff and their accessories (chair, wooden bed, table etc) as per requirement	2	Sets	
13	Covering of Doordarshan OB van with black cloth walling		LS	

14	Arrangement of Jugalbandi stage with all required necessary arrangements	1	No.	
15	Arrangement of gas balloons	200	Nos..	
16	Cleaning of all debris of Open Air Auditorium everyday by 12.00 Noon.		LS	
17	Bamboo with black cloth covering	3000	Sft.	
18	Hoardings-			
a.	04Nos.. X 20'-0" X 10'-0"= 800sqft	800	Sqft	
b.	01no. X 12'-0" X 10'-0"= 120sqft	120	Sqft	
c.	08Nos.. X 10'-0" X 10'-0"= 300sqft	800	Sqft	
d.	Replacement of backlit flex at the entrance of Open Air Auditorium, Konark	120	Sqft	
19	Erection of Selfie Kiosk with back drop 10' x 10', wooden platform with carpeting & light arrangement.	1	No.	
20	Clay Flower Pots (Mari gold)	300	Nos.	
21	CC TV system with all arrangements (Minimum 12 cameras)		LS	
22	Fire Extinguisher	4	Nos.	
			<b>TOTAL - D</b>	

**GRAND TOTAL (A + B + C + D) = Rs. \_\_\_\_\_**

**RUPEES \_\_\_\_\_ ONLY**

**N.B:**

1. All the programme, trial & testing and decoration lighting and sound shall be run on Generator.
2. All rates are quoted for the full period including Stage light, sound and other ancillary arrangement inclusive of trial & testing, transportation, dismantling and cleaning of site but exclusive of taxes.
3. The Generators will operate from 04.00PM for 08hrs for the show and for trial testing on all **07days (i.e. from 29.11.2019 to 05.12.2019)**.
4. The stage light section will be controlled by our appointed Light Designer during the Konark Festival.
5. The stage sound section will be controlled by our appointed Sound specialist during the Konark Festival.
6. The illumination of the temple segment may change as per the instruction of the Light Designer or the authority of OTDC / DOT.
6. Main cables and wires, colour filters, snake cables, Light stands, Speaker stands, Switch Board and Stabilizer and other accessories shall be provided as per requirement.
7. Proper communication systems through walky talky or otherwise among light operator, follow spot operator, sound operator, stage coordinator, light designer, sound specialist etc will be provided by the



tenderer. Sufficient manpower shall be stationed at the venue during the programme hours for coordination and trouble shooting.

8. The successful bidder shall arrange for electricity supply, if required and clearance from the Electrical Inspector at his/her own cost used during the event period without failed.
9. The successful bidder shall produce list of equipments and work done each day at the end of the programme and get it signed from the concern J.E. (Civil), J.E.( electrical) and Officer-in-charge of the festival.
10. The authority reserves the right to increase or decrease the scope of work as per the site requirement in which case, payment shall be made only on the actual work done on unit rate basis.
11. The successful bidder will solely responsible for his/her equipments installed during the event period.
12. Cleaning of premises to be done every day before 02.00PM.

13. **Terms of payment:**

50% of work order value will be released after the completion of the work and handing over the site and the balance payment will be released within 15days from the completion of the event.

14. **Time line for execution of the work:-**

- Mobilization of the materials at the site before 10.00 A.M. of 27.11.2019.
- Completion of fixation and Installation of the equipments etc before 11.00 A.M. of 29.11.2019.
- Handing over of the site after completion of all works before 5.00 P.M. of 29.11.2019.
- Trial run and testing on 29.11.2019 at 06.00 P.M.

15. **Penalty clause:-**

	<b>Timeline for executing of work</b>	<b>Remedies available to OTDC/penalty in case the agency failed to attain the time line.</b>
1.	Mobilization of the material at the site before 10.00A.M. of 27.11.2019	OTDC can execute partly/ fully the work through other agency/ firm and deduct the cost from the amount due to the agency including forfeiting the EMD and the cancelation of work order.
2.	Completion of fixation and Installation of the equipments etc before 11.00A.M of 29.11.2019.	OTDC can execute partly / fully the work through other agency/ firm and deduct the cost from the amount due to the agency including forfeiting the EMD including right to cancel the work order.
3.	Handing over of the site after Completion of all work before 5.00 P.M of 29.11.2019.	Penalty equals to 25% of the work order value to be deducted , in case agency failed to deliver the site before 5.00 P.M of 29.11.2019. In that case, OTDC can execute the work through other agency and the cost to be deducted from the dues of the agency. In addition for each hour of delay beyond 5.00 P.M of 29.11.2019 Rs.5000/- shall be charged as penalty.

16. All legal and labour compliances, maintenance of law and order and fire protection measures in consultation with local and statutory authorities will be the responsible of the Successful bidder.
17. The successful bidder shall be responsible for loss or damage to properties and assets of OTDC or DOT in case of any untoward incidents.

**Superintending Engineer  
OTDC Ltd.**